

# **DECOMMISSIONING IN GERMANY**

Experience, Current Status and Upcoming Challenges



## TÜV NORD NUCLEAR: WHO WE ARE

- TÜV NORD Nuclear is a network of entities operating in the nuclear market, total nuclear staff ±500
- Contracted expert for ministries/regulatory bodies in Germany
- Assessment of licence applications, technical expertise
- Consultants to regulators, operators, and vendors <u>outside</u> <u>Germany</u> covering all relevant aspects in licensing and inspection.
- Tailor-made solutions for training and knowledge transfer.












# LEGISLATION: THE GERMAN WAY




#### NUCLEAR REGULATION: THE GERMAN WAY







## NUCLEAR SUPERVISION: THE GERMAN WAY





## THE PATH TO A LICENSE FOR DECOMMISSIONING

Preliminary Work

- Environmental Impact Study
- Characterization
- Preparation (e.g. Defuelling)



- Application
- Safety Report
- Summary



• Public concerns

Detailed Regulations

- RP
- Waste
- Methods
- Manual
- Etc...

License

- State Authority drafts license
- Federal Authority reviews
- Issued after Review
- State authority supervises execution






# DECOMMISSIONING IN GERMANY: THE STATE OF AFFAIRS






## GERMANY NUCLEAR PHASE OUT TIMELINE











#### NPP Würgassen (BWR) & NPP Stade (PWR)

PreussenElektra, NPP Würgassen

- Components and pipings removed
- To be done: Mainly decontamination & clearance for conventional demolishing and site release
- Stade: Unexpected contamination found inside containment
  - Still more decontamination to be done







#### NPP Rheinsberg (WWER 210), NPP Greifswald (5 units WWER 440)

- Most components removed from all units
  - Steam generators and reactor pressure vessels in interim storage
- Decontamination and clearance
- But: Still some decommissioning work done in auxiliary buildings
- Turbine-hall cleared for conventional use







#### NPP Lingen (BWR with oil-heater)

- Just woke up from safe enclosure (1988-2015)
- VERY unfavourable nuclide-vector (due to <sup>60</sup>Co-decay)
- Preliminary work





#### NPPs Unterweser & Biblis (PWR, moratorium)

- Licenses issued in 2017
- FSD done, defuelling mostly completed
- Currently removal of components, reactor internals and "smaller items"
- In licensing for dismantling of reactor pressure vessel and biological shield





#### NPPs Krümmel & Brunsbüttel (BWR, moratorium)

- In licensing
  - License expected by end of 2018
  - Public hearing pending
- Post-operation
  - Defuelled
  - Construction of interim storage facilities
  - Preliminary work





#### NPPs Emsland, Brokdorf, Grohnde (PWR, 2021-2022)

- Still in operation
- Applied for licenses
  - Ideally, the licenses will be issued before shutdown




# **DECOMMISSIONING PRAXIS**

- Full-System Decontamination
- Removal of Large Components
- Free-Release of a Generator



#### FULL-SYSTEM DECONTAMINATION




175V N(0)?/

17




#### FULL-SYSTEM DECONTAMINATION: PRINCIPLE






## FULL-SYSTEM DECONTAMINATION: RESULTS



TJV NORD

## FULL-SYSTEM DECONTAMINATION: PITFALLS





#### FULL-SYSTEM DECONTAMINATION: PITFALLS









EWN, NPP Greifswald

# Removal of a steam generator in one piece for interim storage on site

- Radiation-Protection
- Crane
- Statics
- Contamination



#### REMOVAL OF A STEAM GENERATOR: FOR INTERIM STORAGE ON SITE



EWN, NPP Greifswald







PreussenElektra, NPP Stade

#### Removal of a steam generator in one piece for off-site processing

- Transport to a facility outside of Germany
- Decontamination by melting
- Partial clearance of the resulting metal
  - Authority required proof that German conditions are met



### FREE RELEASE OF A GENERATOR: TASK

- Non-destructive methods
- Unconditional clearance of all components
- 100 % prove
- Complicated geometries and unreachable cavities
- Cooling system
- Stator: Center & end caps
- Rotor
- Auxiliary units




Vattenfall, NPP Brunsbüttel



## FREE RELEASE OF A GENERATOR: THE COOLING-SYSTEM

- Highly integrated closed-cycle-system
- Branched channels
- Active electronic elements
- Windings, rotor shaft, feedthroughs
- Holistic approach (rotor and stator)
- Sampling of replaceable systems (e.g. PTFE lines, coolant tank, coolant residues)
- Direct measurements at flanges and feedthroughs
- Swipe tests



Vattenfall, NPP Brunsbüttel



## FREE RELEASE OF A GENERATOR: RESULT

- ✓ Potential re-use
- ✓ Reversible Process
- ✓ Non-destructive



Vattenfall, NPP Brunsbüttel

- ✓ 100 % prove either by measurement or alternative methods
- Testing and qualifying procedures for decommissioning
- Documentation





# DECOMMISSIONING: UPCOMING CHALLENGES








- Licensing of moratorium-plants in (long)progress
  - Original staff leaves or retires, diminishing knowledge of the site
- Final disposal and on-site interim-storage
  - No final repository for LAW until at least 2027. For HAW, who knows?
- Conventional waste-streams
  - No public acceptance for released waste on conventional landfills







- Experience in decommissioning is growing in Germany, we are entering a "routine"
- But: Challenges lie ahead
  - No operating final repository yet, thus need for interim storage capacities
  - Many simultaneous projects with limited staff
  - Waning personnel in nuclear
- TÜV NORD EnSys supports a number of D&D-projects, from the initial licensing to the final site-release

